

# **BELVIDERE & DELAWARE RIVER Rwy.**

POST OFFICE BOX 22  
RINGOES, NEW JERSEY 08551

---

## **ADDENDUM No. 1 to REQUEST FOR PROPOSALS Goat Curve MP 14.1+ September 22, 2008**

### **INTRODUCTION**

This Addendum No. 1 is a supplement to and shall be a part of this Railroad's Request for Proposal, dated September 8, 2008, with respect to the subject project.

All proposal shall make reference to this Addendum No. 1 as acknowledgement that the items contained herein are incorporated.

### **BID OPENING**

The bid opening will not be public. The Railroad will review the proposals, prioritize its choices, and send the proposals to the New Jersey Department of Transportation for approval. Contractors will only be notified of the results, after NJDOT review.

### **EXISTING RAIL SIZES**

It should be noted that some of the rail to be replaced is of 100# PS and 96# CNJ section.

### **INSULATED JOINTS**

Contractor shall provide two (2) pair of six-hole Alleghany style encapsulated insulated bars for the approach circuit to River Road and two (2) pair of six-hole Alleghany style encapsulated insulated bars for the approach circuit to Rockafellows Mills Road. Insulated joints shall be new and match the cross section of the rail.

### **RAIL BONDING**

Contractor shall bond rail replaced within the approach circuits of River Road and Rockafellows Mills Road. Approach circuits are approximately 750' in length, from roadway.

## **PROJECT ACCESS**

The railroad will provide project access to its siding at Flemington Bituminous, 205 Pennsylvania Avenue, Flemington, NJ or to the private siding located at 55 River Road at Flemington, NJ.

## **RIVER ROAD**

The grade crossing at River Road has poor visibility. Contractors will not be permitted to put track equipment on or off at this location or load or unload materials at this location. Contractor shall provide qualified flagmen for moving on-track equipment across this public road.

## **RARITAN RIVER BRIDGE 14.1**

Contractor shall install plank walkways across the Raritan River Bridge if workmen will be crossing same on foot. Otherwise, workmen will not be permitted to cross this bridge on foot.

## **EMAIL**

Project Supervisors shall have the ability to communicate with the Railroad General Manager by email at the beginning or end of each work day.

## **NJ SALES TAX**

Please note that this project is exempt from New Jersey Sales Tax. The Railroad will provide a tax exempt certificate upon request.

### **K.BURENGA**

General Manager

Office: 908-782-1611

Fax: 908-782-0134

Email: KBurenga@BRWRR.com